

令和 8 年 度

数 量 計 算 書

町野町真久

数量総括表

[illegible]

[illegible]

土 工 数 量 計 算 表

(工 種) 土工

町野町真久

土質区分		掘削工 (機械)						クラック埋め戻し						切土法面整形					
		断 面				平均断面積	体 積	断 面				平均断面積	体 積	延 長				平均延長	面積
測 点	距 離				断面積						断面積						延長		
BP					0.0												0.0		
縦断NO. 1	5.0				11.2	5.60	28.00										4.8	2.40	12.00
縦断NO. 2	4.0				0.0	5.60	22.40										0.0	2.40	9.60
縦断NO. 3	5.0				1.8	0.90	4.50										4.6	2.30	11.50
EP	6.0				0.0	0.90	5.40										0.0	2.30	13.80
崩壊土BP					0.0														
崩壊土No1	1.60				0.3	0.13	0.21												
崩壊土EP	1.6				0.0	0.13	0.21												
クラック 1	6.2										0.1	0.50							
クラック 2	12.0										0.2	2.88							
合 計	41.40						60.72						3.38						46.90

[illegible]

NO. 1 水路工 数量内訳表					
箇所	番号	計 算 式	数 量	単位	備 考
BF側溝工 (新設)	200型	断面図より	22.9	m	
床掘		0.047×22.9	1.1	m ³	
埋戻し		0.014×22.9	0.3	m ³	
基礎碎石	RC-40 t=10cm	0.03×22.9	0.7	m ³	
間詰モルタル		0.04×22.9	0.9	m ³	
既設水路撤去		0.023×22.9	0.5	m ³	
コンクリート板 撤去		$1/2 \times 0.6 \times 0.7 \times 0.01$	0.0	m ³	
コン殻処分量 (無筋)		$(0.5 + 0.0) \times 2.3$	1.2	m ³	